



WA9 - Raploch Road


WA8 - Dumbarton Road

- Legend:**
- Working Site Boundary
 - P1.1 Carriageway (standard)**
45mm HRA Surf 40/60, whin chips. Assume 20% of hatched area to be planned and resurfaced. Final extent TBC
 - P1.2 Carriageway (cycle street)**
45mm HRA Surf 40/60, silver granite chips
 - P1.3 Carriageway (full construction)**
45mm HRA Surf 40/60, whin chips
 - P1.4 Carriageway setts (reclaimed)**
with stretcher bond edge to kerb and carriageway
 - P1.5 Carriageway setts (natural stone)**
Large sawn setts, silver grey mix
 - P1.6 Carriageway (quiet street)**
45mm HRA Surf 40/60, buff chips
 - P1.7 Concrete Paving (vehicle overrun)**
Block Paving, plain grey / natural smooth
 - P1.9 Carriageway Whin Setts**
Grey whinstone, size to match existing
 - P2.1 Footway (natural stone)**
Caithness slabs 450 / 300 / 600 mm gauge
 - P2.3 Footway (precast concrete)**
Charcon Vianova paving 200 x100 / 400 /200 stretcher bond
 - P2.4 Footway (adopted)**
30mm AC14 HRA Surf with limestone chips
 - P2.5 Block Paving**
200 x 100 x 80mm concrete paving, natural colour
 - P3.1 Cycleway (segregated)**
30mm Ultrapave. Colour: Buff
 - P3.2 Cycleway (carriageway transition)**
30mm Ultrapave. Colour: Green
 - P5.1 Horonizing**
Whin, black
 - K5.2 Side Road Ramp Kerb**
Precast concrete / natural stone
 - K6.1/6.2 Bus Boarder**
Granite / whin (reclaimed)
 - E2.1-2.3 Sett edge**
Reclaimed stone (granite)
 - Existing trees
 - S1.1 Proposed tree planting**
 - S3.1 Amenity grass**
 - S3.2 Wildflower**
 - S4.1 Bulb and woodland carpet planting**
 - S4.3 Low shrub perennial and raingarden**
 - S5.1 Hedge planting**
 - Existing grass - reinstate where any damage associated with construction is caused.

Revision	Date	Description	Initials
P04	24.01.22	For Construction	AKW
P03	20.12.21	For tender	DR
P02	03.08.21	Minor Updates for Tender	JW
P01	22.07.21	For Approval	JW

IronsideFarrar
Environmental Consultants
5th Floor, 135 Buchanan Street, Glasgow G1 2JA
0141 230 2151 | glasgow@ironsidefarrar.com
EDINBURGH | GLASGOW | MANCHESTER

Project No.
40124
Project Name
Walk Cycle Live Stirling
Client
Stirling Council
Title
General Arrangement
Sheet 2 of 4



Date	Paper Size	Quality Assurance					
24.01.22	A1	ISO 9001:2015 SOS UKAS Certificate GB0254539					
Drawn By JW	Checked by RD	Copyright Acknowledgement Ordnance Survey © Crown Copyright 2021 All rights reserved. Licence No. AL100017966					
FOR CONSTRUCTION		Subsidiary C1					
Project	Origin	Location	Type	Role	Class	Number	Revision
40124	IFL	FC	DR	C	10	006	P04

Note: Please do not scale from this drawing